

The Heartland Hotel

The Midwest

Alexis Fons

Construction Management

Advisor: Dr. Leicht



Analysis 1:

9th Story Design Change

Analysis 2:

Link Bridge Prefabrication

Analysis 3:

Structural Lift System

Structural Breadth

Mechanical Breadth

Analysis 4:

Field Labor Experience

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Building Details

Location | The Midwest


Size | 129,416 square feet

Height | 9 stories above grade

Cost | \$40.05 million

Duration | 17 months

June 2015 – October 2016



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Building Details

Location | The Midwest

Size | 129,416 square feet

Height | 9 stories above grade

Cost | \$40.05 million

Duration | 17 months


June 2015 – October 2016



Project Delivery Method

Delivery Method | Design-Build
(Turnkey)

Project Team:



The Heartland Hotel

Background Information

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

9th Story Design Change

Background Information

Locational Information

Occupancy Study

Profitability

Redesign

Cost Analysis

Schedule Analysis

Lifecycle Analysis

Final Recommendation

Analysis 1

9th Story Design Change

Current Design

30 Year City-Improvement Plan

High-End Luxury Rooms

245 Standard Rooms

Opportunity

Include Suites on 9th Story

Goals

↑ Revenue

↑ Variety

↓ Cost

↓ Schedule



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



9th Story Design Change

Background Information

Locational Information

Occupancy Study

Profitability

Redesign


Cost Analysis

Schedule Analysis

Lifecycle Analysis


Final Recommendation

Points of Interest



Point Label	Points of Interest
A	Historic Island
B	River Parkway
C	MLB Field
D	Library
E	Historical Bridge
F	Multi-purpose Arena
G	Historical Society museum
H	Twelve-block Outdoor Mall
J	Art Center
K	Convention Center
Point Label	Public Transportation
1	Light Rail Station
2	Train Station
3	Bus Stop
4	Public Bike Sharing Stations

Nearby Hotels



28 Hotels
within
0.75 miles

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4


Conclusion

9th Story Design Change


- Background Information
- Locational Information**
- Occupancy Study
- Profitability
- Redesign
- Cost Analysis
- Schedule Analysis
- Lifecycle Analysis
- Final Recommendation



Nearby Hotel Prices



Cost per Square Foot



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

9th Story Design Change

Background Information

Locational Information

Occupancy Study

Profitability

Redesign

Cost Analysis

Schedule Analysis

Lifecycle Analysis

Final Recommendation



5 Suite Study

Occupancy Rate	Cost per Suite
100%	\$220
87%	\$325
82%	\$360
72%	\$424
0%	\$950

Normal Occupancy Rate = 72%

10 Suite Study

Occupancy Rate	Cost per Suite
100%	\$220
62%	\$325
52%	\$360
42%	\$424
0%	\$950

A nighttime architectural rendering of the Hatfield Hotel. The building is a modern, multi-story structure with a prominent corner tower featuring a large, illuminated 'HH' logo. The facade is composed of vertical panels, some of which are lit from within, creating a warm glow. The ground floor is brightly lit, showing the entrance and outdoor seating area. The hotel is surrounded by older, darker buildings, creating a contrast between old and new architecture. The street in front of the hotel is visible with some parked cars and a few pedestrians.

Analysis 1


Analysis 2

Analysis 3

Analysis 4

Conclusion

Background Information
Locational Information
Occupancy Study
Profitability
Redesign
Cost Analysis
Schedule Analysis
Lifecycle Analysis
Final Recommendation



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4


Conclusion

9th Story Design Change


- Background Information
- Locational Information
- Occupancy Study
- Profitability**
- Redesign
- Cost Analysis
- Schedule Analysis
- Lifecycle Analysis
- Final Recommendation



Revenue of Suites



Suite Profitability



A nighttime architectural rendering of the Hatfield Hotel. The building is a modern, multi-story structure with a prominent corner and a facade of large, rectangular panels. Many windows are illuminated from within, creating a warm glow. A vertical sign on the corner of the building displays the letters 'HH' in a stylized font. The ground floor is brightly lit, showing the entrance area. The hotel is situated in an urban environment, with older, darker buildings visible in the background. The overall scene is set against a dark, night sky.

Analysis 1

Analysis 2


Analysis 3

Analysis 4

Conclusion

Background Information
Locational Information
Occupancy Study
Profitability
Redesign
Cost Analysis
Schedule Analysis
Lifecycle Analysis
Final Recommendation

The floor plan shows a complex layout of rooms with various square footages. A purple outline highlights a section on the left side of the plan, which includes rooms with the following square footages: 321 sf, 323 sf, 321 sf, 323 sf, 321 sf, 321 sf, 321 sf, 323 sf, 321 sf, 374 sf, and 327 sf. Other rooms in the plan include 257 sf, 422 sf, 63 sf, 324 sf, 321 sf, 324 sf, 321 sf, 324 sf, 321 sf, 399 sf, 320 sf, 320 sf, 323 sf, 87 sf, 332 sf, 396 sf, 320 sf, 320 sf, 320 sf, 320 sf, 320 sf, 320 sf, 330 sf, and 327 sf. The plan also shows a central corridor area and a small room labeled 'ELEVATOR LOBBY'.



The Heartland Hotel

Cost Analysis

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

9th Story Design Change

Background Information

Locational Information

Occupancy Study

Profitability

Redesign

Cost Analysis

Schedule Analysis

Lifecycle Analysis

Final Recommendation

Finishes

Paint

Flooring

Wall Vinyl

Tile

\$6,000

Furnishings

Standard Furniture

Standard Fixtures

Kitchen Equipment

Living Room Furniture

\$8,000

Construction

Wall Studs

Insulation

Drywall

\$19,500

\$33,500 saved



The Heartland Hotel

Schedule Analysis

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

9th Story Design Change

Background Information

Locational Information

Occupancy Study

Profitability

Redesign

Cost Analysis

Schedule Analysis

Lifecycle Analysis

Final Recommendation

Finishes

Paint

Flooring

Wall Vinyl

Tile

90 man-hours

Furnishings

Standard Furniture

Standard Fixtures

Kitchen Equipment

Living Room Furniture

10 man-hours

Construction

Wall Studs

Insulation

Drywall

190 man-hours

9% schedule decrease on the
9th floor

3 day reduction



The Heartland Hotel

Lifecycle Analysis

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

9th Story Design Change

Background Information

Locational Information

Occupancy Study

Profitability

Redesign

Cost Analysis

Schedule Analysis

Lifecycle Analysis

Final Recommendation



	<u>Original Design</u>	<u>Suites Included</u>
Cost to Build	\$40.05 million	\$40.02 million
Revenue per Night	\$35,630/night	\$35,686/night
Cost-to-Run per Night	\$25,755/night	\$25,755/night
Capitalization Rate	9.00%	9.06%
Payback Period (Years)	11.11 years	11.04 years

The Heartland Hotel

Final Recommendation

- Introduction
- Analysis 1**
- Analysis 2
- Analysis 3
- Analysis 4
- Conclusion

9th Story Design Change

- Background Information
- Locational Information
- Occupancy Study
- Profitability
- Redesign
- Cost Analysis
- Schedule Analysis
- Lifecycle Analysis

Final Recommendation

Analysis 1

9th Story Design Change

Goals

- ↑ Revenue ✓
- ↑ Variety ✓
- ↓ Cost ✓
- ↓ Schedule ✓

Recommended



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Link Bridge Prefabrication

Background Information

Crane Logistics



Schedule Analysis

Cost Analysis

Final Recommendation

Analysis 2

Link Bridge Prefabrication



A cross-section of the link bridge and the garage

Background Information

Current Design

62' Link Bridge
Space Limitation

Opportunity

Prefabrication – Modular Unit

Goals

- ↑ Constructability
- ↕ Cost
- ↓ Schedule

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Link Bridge Prefabrication

Background Information


Crane Logistics

Schedule Analysis

Cost Analysis

Final Recommendation

Bridge Components





Ballasted EPDM
Roof

Metal Panels

Garage
Connection

Stucco Finish
Below Bridge

26"x20"
Concrete Piers



A cross-section of the link bridge and the garage

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Link Bridge Prefabrication

Background Information

Crane Logistics

Schedule Analysis

Cost Analysis

Final Recommendation



Crane Logistics

Bridge Weight | 19 tons

Tower Crane


Height/Reach | 213'

Max. Capacity | 7 tons

Hydraulic
Truck Crane

Reach | 231'

Max. Capacity | 100 tons



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4


Conclusion

Link Bridge Prefabrication

Background Information
Crane Logistics
Schedule Analysis
Cost Analysis
Final Recommendation



Schedule Analysis



Productivity

9% Increase in Productivity in Prefabrication Environment

\$6,500 Labor Reduction

The Heartland Hotel

Cost Analysis

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Link Bridge Prefabrication

- Background Information
- Crane Logistics
- Schedule Analysis
- Cost Analysis**
- Final Recommendation



General Conditions Reduction | \$23,800

Labor Reduction | \$6,500

Truck Crane Usage | \$1,400

Transportation Fee | \$2,500

Prefabrication Overhead (3%) | \$2,000

Temporary Pier | \$800

Original Cost | \$79,000

Prefabrication Cost | \$76,000

\$26,500 Savings



7 Day Schedule Reduction

\$27,000 Increased Profit

The Heartland Hotel

Final Recommendation

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4



Conclusion

Link Bridge Prefabrication

- Background Information
- Crane Logistics
- Schedule Analysis
- Cost Analysis
- Final Recommendation**

Analysis 2

Link Bridge Prefabrication



A cross-section of the link bridge and the garage

Goals

- ↑ Constructability ✓
- ↓ Cost ✓
- ↓ Schedule ✓

Recommended



The Heartland Hotel

Background Information

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Structural Lift System

Background Information

Structural Breadth

Systems Design

Mechanical Breadth

Site Logistics

Schedule Analysis

Cost Analysis

Final Recommendation

Analysis 3

Structural Lift System

Current Design

Stucco in winter weather
Limited site space
Renting multiple storage locations

Opportunity

Upbrella Construction lift method

Goals

↑ Constructability
↑ Innovation
↓ Cost
↓ Schedule



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Structural Lift System

Background Information

Structural Breadth
Systems Design
Mechanical Breadth
Site Logistics
Schedule Analysis
Cost Analysis
Final Recommendation




Upbrella Construction

upbrella



Patent Pending - En instance de brevet

Video courtesy of Upbrella Construction
(<https://www.youtube.com/watch?v=q9bKap4FdCc>)



Advantages:

- Move in earlier
- Early landscaping
- Increased safety
- Warm environment (stucco)
- No crane necessary
- More room on site

The Heartland Hotel

Current Construction Method

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Structural Lift System

Background Information

Structural Breadth

Systems Design

Mechanical Breadth

Site Logistics

Schedule Analysis

Cost Analysis

Final Recommendation



Post-tensioned concrete
floors

5 days/floor

1 level of shoring, 2 levels
of re-shoring

Prefabricated column rebar

Tower crane

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Structural Lift System

Background Information

Structural Breadth

Systems Design

Mechanical Breadth

Site Logistics

Schedule Analysis

Cost Analysis


Final Recommendation

PT Concrete
(Current)


Flying forms X

Tendon stressing ?

Delayed column
strength X



Structural Breadth



Loads:

Dead | 10 psf

Live | 40 psf

Deck + Concrete | 37 psf

Joists | 5 psf

Girders | 2 psf

Decking | 1.5VL20, t = 3.25"

Joist | W12x26

Girder | W14x30

Columns | W10x49 (floors 1-9)

W10x33 (roof)



7' taller building

to maintain floor-to-ceiling height

The Heartland Hotel


Introduction
Analysis 1
Analysis 2
Analysis 3
Analysis 4
Conclusion




Structural Lift System

Background Information
Structural Breadth
Systems Design
Mechanical Breadth
Site Logistics
Schedule Analysis
Cost Analysis
Final Recommendation

Hydraulic Cylinders



Protection Shell



Polycarbonate Panels:

OSHA
Light Transmission
High R-Value

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Structural Lift System

- Background Information
- Structural Breadth
- Systems Design
- Mechanical Breadth**
- Site Logistics
- Schedule Analysis
- Cost Analysis
- Final Recommendation

Mechanical Breadth

Concrete Requirements: 55°F

Original Method

Material	Square Footage	R-Value	U-Value	Temperature Change	Total Btu/hr
Tarp	6,240	0.071	14.11	28.5	2,509,322
Formwork (3/4" plywood)	14,596	0.94	1.06	28.5	442,538
Concrete (NW 6.57" thick)	14,596	0.47	2.13	28.5	885,077
Total Btu/hr for total construction:					3,836,937
This is equivalent to 4 heaters					

Stucco Requirements: 40°F

Original Method

Material	Square Footage	R-Value	U-Value	Temperature Change	Total Btu/hr
Tarp (between scaffolding and building)	6,240	0.071	14.11	10.4	915,683
Tarp (exterior)	6,600	0.071	14.11	10.4	968,510
Scaffolding Wood Planks (1.5" thick)	6,438	1.88	0.53	10.4	35,614
Total Btu/hr for total construction:					1,919,807
This is equivalent to 2 heaters					

The Heartland Hotel

Mechanical Breadth

Systems Comparison

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Structural Lift System

Background Information

Structural Breadth

Systems Design

Mechanical Breadth

Site Logistics

Schedule Analysis

Cost Analysis

Final Recommendation



Constant Heating: 55°F

Proposed Method

Material	Square Footage	R-Value	U-Value	Temperature Change	Total Btu/hr
Polycarbonate Panels	17,079	2.000	0.50	27.5	234,836
Plywood Planks (1.5")	3,219	1.880	0.53	27.5	47,086
Concrete (3.25")	14,596	0.260	3.85	27.5	1,543,808
Roof	14,596	24.000	0.04	27.5	16,725
Metal Deck	14,596	0.000	N/A	27.5	-
Solar Heat Gain Coefficient	N/A	N/A	N/A	N/A	(63,749)
Total Btu/hr for total construction:					1,778,706
This is equivalent to 2 heaters					

Original Method

Concrete at 55°F
Stucco at 40°F

140 days
of heat

\$21,100

Structural Lift Method

Both systems at
55°F

136 days
of heat

\$19,500

\$1,600

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Structural Lift System

Background Information

Structural Breadth

Systems Design

Mechanical Breadth

Site Logistics

Schedule Analysis

Cost Analysis

Final Recommendation



Site Plan: *Original*



Site Plan: *Proposed*



The Heartland Hotel

Schedule Analysis

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Structural Lift System

Background Information

Structural Breadth

Systems Design


Mechanical Breadth

Site Logistics

Schedule Analysis

Cost Analysis

Final Recommendation



Original Method:

291 days

5 days/floor of structure

Proposed Method:

258 days – 7 weeks shorter

11 days per floor overall

9% productivity increase

Interior Activities – additional overlap

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Structural Lift System

- Background Information
- Structural Breadth
- Systems Design
- Mechanical Breadth
- Site Logistics
- Schedule Analysis
- Cost Analysis**
- Final Recommendation

Cost Analysis

Category	Cost Change (Original - Proposed)
Construction Enclosure System	\$(75,588.59)
Heating System	\$ 1,620.88
Structure	\$(629,535.65)
Equipment	\$(119,816.39)
Exterior Enclosure	\$(171,937.81)
General Conditions	\$112,111.93
Total	\$(883,145.63)

\$883,000 cost increase



33 Day Schedule Reduction

\$170,000 Increased Profit

The Heartland Hotel

Final Recommendation

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Structural Lift System

Background Information

Structural Breadth

Systems Design

Mechanical Breadth

Site Logistics

Schedule Analysis

Cost Analysis

Final Recommendation

Analysis 3

Structural Lift System

Goals

↑ Constructability ✓

↑ Innovation ✓

↓ Cost X

↓ Schedule ✓

Not Recommended



The Heartland Hotel

Background Information

- Introduction
- Analysis 1
- Analysis 2
- Analysis 3
- Analysis 4**
- Conclusion

- Field Labor Experience
- Background Information
- Current Position
- Education
- Success as a Superintendent
- Final Recommendation

Analysis 4

Field Labor Experience



What benefits does field labor experience provide for a career as a superintendent?

How does field labor impact the role and success of a superintendent?



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Field Labor Experience

Background Information


Current Position

Education

Success as a Superintendent

Final Recommendation

Current Position



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Field Labor Experience

Background Information


Current Position

Education

Success as a Superintendent

Final Recommendation

Level of Education



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Field Labor Experience

Background Information


Current Position

Education

Success as a Superintendent

Final Recommendation

Level of Education



31% of all respondents received a degree

The Heartland Hotel

Superintendent Level of Education

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion

Field Labor Experience


Background Information

Current Position

Education

Success as a Superintendent

Final Recommendation



48% of superintendents received a degree

Construction Management and Civil Engineering

52% of superintendents went into the field

Carpentry (48%)

The Heartland Hotel

Success as a Superintendent

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion




Field Labor Experience

Background Information
Current Position
Education

Success as a Superintendent

Final Recommendation

Experiences which are beneficial to becoming a superintendent



Experience Working with Drawings and Specifications

4.9/5

Experience Working in a Trade

4.5/5

Taking Leadership Classes

4.3/5

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Field Labor Experience

Background Information
Current Position
Education

Success as a Superintendent

Final Recommendation

Success as a Superintendent

Importance of skills/attributes for becoming a superintendent

	More Important		Equally Important		More Important		
The Ability to Teach							The Ability to Learn
Verbal Communication							Written Communication
Field Experience							Office Experience
Time Management							People Management
Field Credibility							Educational Credibility
People-Focus							Goal-Focus
Leading by Example							Leading by Direction
Identifying Resources/Opportunities							Identifying Personality Traits and Abilities
Understanding People							Understanding Systems
The Ability to Work with a Team							The Ability to Work Autonomously

Office vs. Field Experience

Importance of Relationships

Office vs. Field Experience

Field Experience

Field Credibility

Importance of Relationships

Verbal Communication

The Ability to Work with a Team

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Field Labor Experience

Background Information

Current Position

Education

Success as a Superintendent

Final Recommendation

Analysis 4

Field Labor Experience

Final Recommendation

Field Labor
Field and Office Work
Office Work



Superintendent

According to current superintendents,

**field labor experience is more valuable
for a career as a superintendent.**

Those receiving a higher education – **go out and build.**

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4


Conclusion



Analysis 1



9th Story Design Change

Recommended



Analysis 2

Link Bridge Prefabrication




Analysis 3

Structural Lift System

Analysis 4

Field Labor Experience



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Analysis 1

9th Story Design Change


Recommended



Analysis 2


Link Bridge Prefabrication

Recommended




Analysis 3

Structural Lift System



Analysis 4

Field Labor Experience



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Analysis 1

9th Story Design Change



Recommended



Analysis 2

Link Bridge Prefabrication

Recommended




Analysis 3

Structural Lift System

Not Recommended

Analysis 4

Field Labor Experience



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Analysis 1

9th Story Design Change


Recommended



Analysis 2

Link Bridge Prefabrication


Recommended



Analysis 3

Structural Lift System


Not Recommended



Analysis 4

Field Labor Experience

Extremely Beneficial



The Heartland Hotel

The Midwest

Thank you

Jesus
PSU AE Faculty
Mortenson Construction
DPR Construction
Family and Friends



Analysis 1:

9th Story Design Change

Analysis 2:

Link Bridge Prefabrication

Analysis 3:

Structural Lift System

Structural Breadth

Mechanical Breadth

Analysis 4:

Field Labor Experience

9th Story Design Change Appendix

The Heartland Hotel

Mortenson Development Inc.

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Partial Owner

Considerations

240-250 rooms

Standard Rooms Only

245 rooms ✓

Type of Guest

Business Personnel ✓

Construction
Cost/SF

\$253/SF ✓

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Nearby Hotel Prices

Company X Hotel Suites



All Nearby Suites



The Heartland Hotel

5 Suite Study

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



\$220 ----> 100%


\$360 ----> 82%

\$950 ----> 0%

Cost per Suite	Occupancy Rate
\$220	100%
\$325	87%
\$360	82%
\$424	72%
\$950	0%

Normal Occupancy Rate = 72%

5 Suites



The Heartland Hotel

5 Suite Study

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



\$220 ----> 100%


\$360 ----> 82%

\$950 ----> 0%

Cost per Suite	Occupancy Rate
\$220	100%
\$325	87%
\$360	82%
\$424	72%
\$950	0%

Normal Occupancy Rate = 72%

Revenue of 5 Suites



The Heartland Hotel

10 Suite Study

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



\$220 ----> 100%


\$360 ----> 52%

\$950 ----> 0%

Cost per Suite	Occupancy Rate
\$220	100%
\$325	62%
\$360	52%
\$424	42%
\$950	0%

Normal Occupancy Rate = 72%

10 Suites



The Heartland Hotel

10 Suite Study

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



\$220 ----> 100%


\$360 ----> 52%

\$950 ----> 0%

Cost per Suite	Occupancy Rate
\$220	100%
\$325	62%
\$360	52%
\$424	42%
\$950	0%

Normal Occupancy Rate = 72%

Revenue of 10 Suites



Link Bridge Appendix

The Heartland Hotel

Advantages and Disadvantages

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



On-Site Construction

Standard method ✓

Later design possible ✓

1'6-2'6 gap – doesn't fit men/equipment ✗

Safety hazards ✗

Weather delays ✗

Prefabrication

Panels

Small delivery truck ✓

Lighter crane pick ✓

Quality control ✓

Limited access ✗

Integrity of seams ?

Attachment methods ?

No interior finishes ?

3D Module

Complete entire unit ✓

Design already created ✓

Minimal site construction ✓

Best quality control ✓

Larger pick ?

Larger truck ?

The Heartland Hotel

Connections

Introduction



Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Heartland Hotel Budget

ACTUAL BUDGET	COST
Foundations	\$ 713,268.10
Superstructure	\$ 4,474,147.48
Exterior Enclosure	\$ 2,341,547.31
Roofing	\$ 400,820.83
Interior Construction	\$ 8,111,096.92
Interior Finishes	\$ 3,231,833.54
Conveying & Chutes	\$ 807,362.00
Mechanical	\$ 5,176,729.00
Fire Protection	\$ 296,887.50
Electrical	\$ 2,081,009.59
Low Voltage	\$ 757,500.00
Equipment	\$ 25,500.00
Building Demolition	\$ 7,167.73
Site Preparation	\$ 466,617.23
Site Improvements	\$ 147,464.00
Site Electrical Utilities	\$ 81,950.00
Site Services	\$ 541,870.30
Furniture, Fixtures & Equipment (FF&E)	\$ 3,411,740.28
Operating Supplies & Equipment (OS&E)	\$ 830,015.03
General Conditions/Staff	\$ 1,732,638.90
Permits & Street/Sidewalk Closure Fees	\$ 573,166.00
Third Party Inspections/Testing	\$ 160,000.00
Design Fees	\$ 950,000.00
Insurance	\$ 351,558.00
Design Builders Fee	\$ 1,071,898.00
Estimating & Construction Contingency	\$ 1,306,212.00
Total:	\$ 40,049,999.74

Structural Lift Method Appendix

The Heartland Hotel

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Upbrella Construction Breakdown




Figure 3.4: This patent pending sequence is courtesy of Upbrella Construction (<http://www.3l-innogenie.com/en/upbrella>).

Schedule Break Down

Task Name	Duration
Floor Structure	11 days
Construct Floor Framing (Joists and Girders)	5 days
Lift and Install Columns	1 day
Lower System onto Columns	1 day
Finalize Structure (Stairs, Elevator Framing, Rebar, Inspection)	5 days
Pour Floor Concrete	1 day
Wall Enclosure Systems	11 days
Exterior Infill Framing	8 days
Install Stucco	9 days
Install Metal Panels	9 days
Install Glazing Systems	9 days

The Heartland Hotel

Cost Breakdown

- Introduction
- Analysis 1
- Analysis 2
- Analysis 3
- Analysis 4
- Conclusion




	Category	Material	Description	Amount	Floor Multiplier	Unit	R.S. Means page	Labor-Hour	Material	Labor	Equipment	Total	Areas Totaled	Man-Hours
Structural Uplift System (Proposed Method)	Construction Enclosure System	Polycarbonate Panels	Walls and ceiling	17079.0	1	sf		0.107	\$ 1.26	\$ 5.64		\$ 117,722.13	\$ 224,233.26	1,827.45
		7' Aluminum with plywood planks	Floor	88.6	1	ea.		0.33	\$ 115.69	\$ -		\$ 10,250.13		29.24
		Steel Columns (W10x33)		2310.0	1	lf	310	0.093	\$ 32.19	\$ 5.61	\$ 2.78	\$ 93,747.47		214.83
		Guardrails	Portable metal with base pads	624.0	1	lf		0.027	\$ 2.57	\$ 1.46		\$ 2,513.52		16.85
	Heating System	Heaters	136 days of heat	4.5	1	month		0	\$ -	\$ -	\$ 1,300.00	\$ 5,893.33	\$ 19,592.80	-
		Propane for Heaters	8.25 GPH at 81%	7270.6	1	Gallons		0	\$ 1.88	\$ -	\$ -	\$ 13,699.47		-
	Structure	1.5VL20 decking	22 ga., 2" galvanized	14596.0	8	sf	168	0.009	\$ 2.46	\$ 0.55		\$ 352,200.31	\$ 1,834,730.94	1,050.91
		Concrete topping (3.25")	Lightweight	14596.0	8	sf	97	0.022	\$ 1.25	\$ 1.06	\$ 0.27	\$ 300,392.69		2,568.90
		WWF (6x6, W1.4xW1.4)		146.0	8	csf	95	0.457	\$ 14.59	\$ 27.58		\$ 49,234.06		533.63
		Joists (W12x16)		1793.0	8	lf	158	0.064	\$ 23.64	\$ 3.82	\$ 1.74	\$ 418,928.14		918.02
		Girders (W14x30)		965.0	8	lf	158	0.062	\$ 43.76	\$ 3.74	\$ 1.70	\$ 379,838.51		478.64
		Columns (W10x33 - roof)		517.0	1	lf	158	0.093	\$ 32.19	\$ 5.61	\$ 2.78	\$ 20,981.58		48.08
		Columns (W10x49 - all other levels)		485.7	8	lf	158	0.102	\$ 71.93	\$ 6.11	\$ 2.55	\$ 313,155.66		396.33
	Equipment	Double Girder Bridge Crane	2 Girder, 50' span, 3 ton	2.0	1	ea.	1200	72	\$ 46,753.00	\$ 4,766.03	\$ 355.00	\$ 103,748.05	\$ 264,680.39	144.00
		Hydraulic Cylinders		7.0	1	ea.		0	\$ 12,492.01	\$ -		\$ 87,444.04		-
		Material Hoist	2 for 5 months	10.0	1	month	1335	0	\$ 2,892.25	\$ -	\$ -	\$ 28,922.50		-
		Mast-Climbing Platform	2 for 4 months, 50' wide, less than 100' tall, rent	8.0	1	mast*month	21	0	\$ 3,118.60	\$ -	\$ -	\$ 24,948.80		-
Street Cranes		Truck mounted, 150 tons, 18' radius	10.0	1	days		0	\$ 1,961.70	\$ -	\$ -	\$ 19,617.00	-		
Façade	Additional Exterior Enclosure Installation	7' taller building w/624' perimeter; added price is a multiple of the original exterior enclosure cost	4368.0	1	sf		0.28	\$ -	\$ -	\$ -	\$ 171,937.81	\$ 171,937.81	1,223.04	
Profit	Profit from Opening	Opens 1.5 months earlier	0.0	0			0	\$ -	\$ -	\$ -	\$ (170,169.00)	\$ (170,169.00)	-	
Total:												\$ 2,345,006.19	\$ 2,345,006.19	9,449.91
Original Construction Method	Construction Enclosure System	Scaffolding Framing Erection	6-12 stories, 6'4x5	32.9	10.6	100sf	19	3.6	\$ 35.21	\$ 196.28		\$ 80,728.53	\$ 148,644.67	1,255.46
		Scaffolding planks 2"x10"x16'	Average cost of below and above 50'	241.0	10.6	ea.	20	0.333	\$ 6.04	\$ 18.34		\$ 62,282.94		850.68
		Scaffolding Tarp	Polyethylene sheet	59.7	7	100sf	23	0.216	\$ 4.00	\$ 9.47		\$ 5,633.20		90.29
	Heating System	Heaters	140 days of heat at 87%	4.7	1	month		0	\$ -	\$ -	\$ 1,300.00	\$ 6,066.67	\$ 21,213.68	-
		Propane for Heaters	8.25 GPH at 87%	8038.8	1	Gallons		0	\$ 1.88	\$ -	\$ -	\$ 15,147.01		-
	Structure	Concrete Slab	6" elevated	14596.0	8	sf	98	0.022	\$ 2.04	\$ 1.06	\$ 0.27	\$ 393,192.89	\$ 1,205,195.30	2,568.90
		PT Formwork	Multiple by number of forms - 4 uses, so 2x floor	14596.0	3	sf	76	0.086	\$ 1.19	\$ 4.59		\$ 253,061.80		3,765.77
		PT Tendons		9075.0	8	lb.	95	0.027	\$ 0.61	\$ 1.63	\$ 0.03	\$ 165,114.18		1,960.20
		Slab Rebar	Elevated slabs, #4-#7	860.0	8	lb.	93	0.006	\$ 0.50	\$ 0.34	\$ -	\$ 5,770.39		41.28
		Column Concrete	16x16, less than 2% reinf, 9.57'	30.5	9	cy	97	0	\$ 283.69	\$ 677.44	\$ 46.00	\$ 276,818.93		-
		Column Rebar	#3-7 Column Rebar	19936.5	1	lb.		0.011	\$ 0.50	\$ 0.65	\$ -	\$ 22,936.10		219.30
		Column Rebar	#8=18 Column Rebar	95703.7	1	lb.		0.007	\$ 0.50	\$ 0.42	\$ -	\$ 88,301.01		669.93
	Equipment	Tower Crane		7.5	1	month	1334	0	\$ 17,001.40	\$ -	\$ -	\$ 127,510.50	\$ 144,864.00	-
		Material Hoist	6 months	6.0	1	month	1335	0	\$ 2,892.25	\$ -	\$ -	\$ 17,353.50		-
	Total:												\$ 1,519,917.64	\$ 1,519,917.64
Comparative Total (Proposed - Original):												\$ 825,088.55	\$ 825,088.55	(1,971.89)

The Heartland Hotel


- Introduction
- Analysis 1
- Analysis 2
- Analysis 3
- Analysis 4
- Conclusion



Original Schedule



Proposed Schedule



The Heartland Hotel

Structural Breadth Calculations

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Decking

Requirements:

- Composite decking because:
 - Thinner
 - More economic use of materials
 - Efficient
- 3-1/4" topping for fireproofing for lightweight concrete
- 3-spans
- 8'2 spacing
- Unshored

Loads taken from the structural drawings:

- Live Load – 40psf for rooms and corridors above the 2nd floor
- Wind Load – N/A
- Dead Load – assumed 10pst

Total Load = Dead + Live

50psf = 10 + 40

Decking chosen from Vulcraft Steel Roof and Floor Deck catalog:

1.5VL20 with lightweight concrete

4.75" deep

t=3.25" (for fireproofing)

37psf = concrete + deck self-weight

Recommended Welded Wire Fabric: 6x6 – W1.4xW1.4

Maximum superimposed load with a 8'6 clearspan: 200psf ✓

Joist

Loads:

- Deck and Concrete load = 37psf
- Joists = Assumed 5psf
- Superimposed dead load = 10psf
- Live load = 40psf
 - Live Load reduction: $K_{LL}A_T = 8'2 \times 2 \times 23'8 = 387 < 400$ – not reducible

Load Combinations:

- Dead: 37+5+10=52psf
- Live: 40psf

1.4D = 75.6psf

1.2D+1.6L = 126.4psf – controls

Check Decking:

126.4psf < 200psf limit ✓

Weight:

$W_u = 126.4psf \times \frac{8'2}{1000 \frac{lb}{kip}} = 1.03 klf$

Moment:

$M_U = \frac{wl^2}{8} = \frac{(1.03klf)(23'8)^2}{8} = 72.11ft \cdot kips \rightarrow W12 \times 16$

$M_U = 72.11 \leq 75.4 = \phi M_n$ ✓

Shear:

$V_U = \frac{wl}{2} = \frac{(1.03klf)(23'8)}{2} = 12.19kips$

$V_U = 12.19 \leq 79.2 = \phi V_n$ ✓

Check Self Weight Assumption:

Assumed 5psf > $\frac{16lbs}{8'2} = 1.96$ ✓

Final Design:

W12x16

Girder

Spacing:

$\frac{18'5+23'8}{2} = 21.04'$

Span = 24'5

Loads:

- Deck and Concrete load = 37psf
- Joists = 5psf
- Superimposed dead load = 10psf
- Girders = Assumed 2psf
- Live load = 40psf

Live Load reduction

$L = 0.4L_0$ -or-

$L = L_0 \times \left(0.25 + \frac{15}{\sqrt{K_{LL}A_T}}\right) = L_0 \times \left(0.25 + \frac{15}{\sqrt{(24'5 \times 21.04 \times 2)}}\right) = 0.72L_0$ – controls

Live Load = 40*0.72 = 28.72psf

Dead Load = 37+5+10+2 = 54psf

Load Combinations:

1.4D = 75.6psf

1.2D+1.6L = 110.75psf – controls

Weight:

$W_u = 110.75psf \times \frac{21.04'}{1000 \frac{lb}{kip}} = 2.33klf$

Moment:

$M_U = \frac{wl^2}{8} = \frac{(2.33klf)(24'5)^2}{8} = 173.64ft \cdot kips \rightarrow W14 \times 30$

$M_U = 173.64 \leq 177 = \phi M_n$ ✓

Shear:

$V_U = \frac{wl}{2} = \frac{(2.33klf)(24'5)}{2} = 28.45kips$

$V_U = 28.45 \leq 112 = \phi V_n$ ✓

Check Self Weight Assumption:

Assumed 2psf > $\frac{30lbs}{21.04'} = 1.43$ ✓

Final Design:

W14x30

Columns

Area:

$A_T = 24'5 \times \frac{23'8+18'5}{2} = 513.73 sf$

Loads:

- Deck and Concrete load = 37psf
- Joists = 5psf
- Superimposed dead load = 10psf
- Girders = 2psf
- Snow Load = 16psf
- Live load = 40psf
- Number of stories: 1 through 9 and the roof = 8 + roof

Live Load reduction

$L = 0.5L_0$ - controls

$L = L_0 \times \left(0.25 + \frac{15}{\sqrt{K_{LL}A_T}}\right) = L_0 \times \left(0.25 + \frac{15}{\sqrt{(8 \times 4 \times 513.73)}}\right) = 0.37L_0$

Live Load = 40*0.5 = 20psf

Dead Load = 37+5+10+2 = 54psf

Load Combinations for the Roof:

1.2D + 1.6L + 0.5S = 128.8psf – controls

128.8psf * 513.73 sf = 66,168 lbs = 66.17kips – for the roof

Load Combinations for the Floors:

1.2D + 1.6L = 90.4psf – controls

128.8psf * 513.73 sf = 66,168 lbs = 66.17kips – for the roof

(Number of Stories)*(90.4psf)*(513.73sf) / 1000 + 66.17 = Total Load

Columns for Floors	Number of Stories	Total Load (Kips)	Column Design Size	Pult ³
1-2	8	438	W10x49	532 kips ✓
2-3	7	392		
3-4	6	345		
4-5	5	299		
5-6	4	252		
6-7	3	206		
7-8	2	160		
8-9	1	113	W10x33	311 kips ✓
9-Roof	0	66.17		

The Heartland Hotel

Introduction

Analysis 1

Analysis 2



Analysis 3

Analysis 4

Conclusion



Mechanical Breadth

SPECIFICATIONS	THP-1000	THP-1100
		
BTU / HR	48,600	48,600
MINIMUM	1,000,000	1,100,000
MAXIMUM		
CFM	6,000	6,000
NATURAL GAS	1" NPT	1" NPT
PROPANE	1" NPT	1" NPT
POWER		
SUPPLY	230/1/60/25*	230/1/60/25*
V/PH/HZ/A		
DIMENSIONS		
L x W x H (IN)	76x35x69	80x36x71
WEIGHT (LBS)	939	889
BASE	CASTERS	CASTERS

<http://temp-air.com/heating/direct-fired-heaters-th/>

Month	Temperature Range (°F)	Average Temperature (°F)
November	26-41	33.5
December	12-27	19.5
January	8-24	16
February	13-29	21
March	24-41	32.5
April	37-58	47.5

The Heartland Hotel

- Introduction
- Analysis 1
- Analysis 2
- Analysis 3
- Analysis 4
- Conclusion



ACI 306R-10 Guide to Cold Weather Concreting

(ACI 302.1R). Keep the temperature of concrete as placed as close to the recommended minimum value as practicable.

Preparation before concrete is placed requires a temperature increase of the formwork, reinforcement, and other surfaces that will contact fresh concrete so the temperature of the freshly placed concrete will not decrease below the minimums as placed and maintained (Table 5.1). There are many techniques for warming formwork and embedded items, including heated enclosures, electric blankets, hydronic heating systems, or other acceptable means. Best practice indicates that all surfaces should be above the freezing temperature of water. However, take care to limit surface temperatures to no more than 10°F (5°C) greater or 15°F (8°C) less than that of the concrete to avoid inconsistent setting, rapid moisture loss, and plastic shrinkage cracking.

Table 5.1—Recommended concrete temperatures					
		Section size, minimum dimension			
		< 12 in. (300 mm)	12 to 36 in. (300 to 900 mm)	36 to 72 in. (900 to 1800 mm)	> 72 in. (1800 mm)
Line	Air temperature	Minimum concrete temperature as placed and maintained			
1	—	55°F (13°C)	50°F (10°C)	45°F (7°C)	40°F (5°C)
		Minimum concrete temperature as mixed for indicated air temperature*			
2	Above 30°F (–1°C)	60°F (16°C)	55°F (13°C)	50°F (10°C)	45°F (7°C)
3	0 to 30°F (–18 to –1°C)	65°F (18°C)	60°F (16°C)	55°F (13°C)	50°F (10°C)
4	Below 0°F (–18°C)	70°F (21°C)	65°F (18°C)	60°F (16°C)	55°F (13°C)
5	—	Maximum allowable gradual temperature drop in first 24 hours after end of protection			
		50°F (28°C)	40° (22°C)	30°F (17°C)	20°F (11°C)

*For colder weather, a greater margin in temperature is provided between concrete as mixed and required minimum temperature of fresh concrete in place.

7.1—Protection methods
Protect concrete from freezing as soon as practicable after placement, consolidation, and finishing. This protection can be provided by concrete mixture acceleration, insulation, heat systems, enclosures, or a combination of these practices, and should be planned before placement. *Accelerating the*

Table 7.1—Length of protection period for concrete placed during cold weather			
Line	Service condition	Protection period at minimum temperature indicated in Line 1 of Table 5.1, days*	
		Normal-set concrete	Accelerated-set concrete
1	No load, not exposed	2	1
2	No load, exposed	3	2
3	Partial load, exposed	6	4
4	Full load	Refer to Chapter 8	

*A day is a 24-hour period.

The Heartland Hotel

Cost Analysis

Introduction

Analysis 1

Analysis 2

Analysis 3

Analysis 4

Conclusion



Category	Original Method	Structural Uplift Method	Cost Change (Original - Proposed)
Construction Enclosure System	\$148,644.67	\$224,233.26	\$(75,588.59)
Heating System	\$21,213.68	\$19,592.80	\$ 1,620.88
Structure	\$1,205,195.30	\$1,834,730.94	\$(629,535.65)
Equipment	\$144,864.00	\$264,680.39	\$(119,816.39)
Exterior Enclosure	\$0	\$171,937.81	\$(171,937.81)
General Conditions	\$0	\$(112,111.93)	\$112,111.93
Total	\$1,519,917.64	\$2,556,279.89	\$(883,145.63)

\$883,000 cost increase



33 Day Schedule Reduction

\$170,000 Increased Profit

Structural Lift Method Appendix

The Heartland Hotel

Introduction

Analysis 1

Analysis 2


Analysis 3

Analysis 4

Conclusion



Years in Current Position



Years in Construction Industry

